

Name of work :- A/Mtc. of Sewerage disposal in I/A Dharuhera. “Prov. & fixing steel jal on sump

well at sewerage disposal in I/A Dharuhera and all other works contingent thereto”.

Rs. 1.80 Lacs

A/C

CONTRACT SCHEDULE OF RATES

Sr. No/HSR Item	Description	Qty	Unit	Rate
1/18.1	Steel work fixed independently without connecting plates, including cutting hosting and fixing in position in :- R.S. Joists.	12.00	qtl	Rs.
1011.45				
2/18.12	Wrough iron and mild steel (using angles flats, square bars, tees and channels) ladders grills grating framesw window guards, iron doors openable or fixed stair case or parapet or any other type of railing.	27.00	qtl	Rs.
1040.35				
3/11.27	First class brick work laid in cement stone dust (from crusher) mortar 1:6 in first storey upto4 metres above plinth level.	2.50	cum	Rs.
434.55				
4/10.41	Cement conc. 1:2:4 with stone agg. 20mm nominal size in foundation and plinth.	1.00	cum	Rs.
615.60				

Rewari

Executive Engineer,
HUDA Division,

Name of work :- A/Mtc. of Sewerage disposal in I/A Dharuhera. "Prov. & fixing steel jal on sump well at sewerage disposal in I/A Dharuhera and all other works contingent thereto".

A/C Rs. 1.80 Lacs

ABSTRACT OF COST

Sr, No/HSR Item	Basic Cost	C.P	Amt. due to C.P	Total Amount
1/18.1	Rs. 12137.00	325%	Rs. 39446.00	Rs. 51583.00
2/18.12	Rs. 28089.00	325%	Rs. 91291.00	Rs. 119380.00
3/11.27	Rs. 1086.00	400%	Rs. 4345.00	Rs. 5431.00
4/10.41	Rs. 615.60	340%	Rs. 2093.00	Rs. 2709.00

Total				Rs. 179103.00

Say : Rs. 1.80 Lacs

Rewari

Executive Engineer,
HUDA Division,

