

Name of work :- Const. of parking & pavements in Sec-3 S/Centre Rewari. “Prov. and laying of 25mm thick premix carpet with tack coat and seal coat with mechanically mixer and all other works contingent thereto”.

A/C Rs. 2.00 Lacs

CONTRACT SCHEDULE OF RATES

| Sr. No/HSR Item | Description | Qty | Unit | Rate |
|-----------------|---|----------|------|------------|
| 1/App. Item | Providing and laying of tack coat on existing black top surface with bitumen 50 kg per 100 sqm including cost of bitumen. | 1045 Sqm | Sqm | Rs. 17.90 |
| 2/App.Item | Prov. and laying Compacted 75mm thick BUSG consisting of course agg. @ 10 cum & key agg. @ 1.30 cum per 100 sqm surfacing area with bitumen mixing @ 50 kg for tack coat layer and 150kg for Ist layer plus 150 kg for spray of BUSG layer IInd layer per 100 sqm area including cost of laying and consolidation and rolling with road roller complete as per PWD specification bitumen will bearranged by the Contractor at his own cost. | 200 sqm | Sqm | Rs. 215.90 |
| 3/App. Item | Providing & Laying 25 mm premix carpet using tar of bitumen grade 80/100 as binder using 1.82 kg/sqm for all operaton binder and agregate heated and mixed with mechanical mixed in a designed proportion using stone agregate @ 3.40 cum per 100 sqm(i.e. bajri 13.2mm @ 2.30 & 11.2 mm @ 1.10 cum) Laying and rolling to standard specifiction complete and night watchman and including cost of all material i.e Bajri and bitumen, Bitumenwill be arranged by the Contractor. | 1045 Sqm | Sqm | Rs. |
| 100.00 | | | | |
| 4/App.Item | Providing and laying of tack type B including cost of bitumen of grade 80/100 @ 0.68kg/sqm and fine agg. mixed and heated with mechanical mixer with cost of stone dust 2.36mm-180micron @ 0.60 cum per 100sqm including cost of bitumen/binder. Bitumen shall be arranged by the contractor. | | | |

32.00

1045 Sqm

Sqm

Rs.

Executive Engineer,
HUDA Division,
Rewari.

Name of work :- Const. of parking & pavements in Sec-3 S/Centre Rewari. "Prov. and laying of 25mm thick premix carpet with tack coat and seal coat with mechanically mixer and all other works contingent thereto".

A/C Rs. 2.00 Lacs

ABSTRACT OF COST

| Sr, No/HSR Item | Basic Cost | C.P | Amt. due to C.P | Total Amount |
|--------------------|---------------|-----|-----------------|---------------|
| 1/App.Item | Rs. 18706.00 | - | - | Rs. 18706.00 |
| 2/App.Item | Rs. 43180.00 | - | - | Rs. 43180.00 |
| 3/App.Item | Rs. 104500.00 | - | - | Rs. 104500.00 |
| 4/App.Item | Rs. 33440.00 | - | - | Rs. 33440.00 |
| | | | | Total |
| | | | | Rs. 199826.00 |

Say : Rs. 2.00 Lacs

Executive Engineer,
HUDA Division,
Rewari.

